

Anexa 1

Lucrari la instalatia electrica pentru alimentarea cu energie electrica a unitatilor de climatizare din locatia strada Cicio Pop nr.13

Nr.	Cod	Denumire produs/operatie	UM	Cantitate	Pret unitar	Valoare
1		TABLOU METALIC 800X600X250 ECHIPAT CU SEPARATOR DE SARCINA 3 POLI 250A SI 20 SIGURANTE AUTOMATE 10A 1P+N C 4,5KA	B	1		0.00
2		PRIZA DE PAMANT $R \leq 4 \Omega$	B	1		0.00
3		CABLU ACYABY 3X150+70	M	5		0.00
4		SET MANSON ALUMINIU 3X150+70	B	1		0.00
5		CANAL ZINCAT 150X60 PERFORAT CU CAPAC SI SUPORTI FIXARE PERETE	M	60		0.00
6		CABLU CYY-F 3X2,5	M	400		0.00
7		CABLU CYY-F 3X4	M	400		0.00
8		CADRU APARENT 2 L CU PROTECTIE IP 55 ECHIPATA CU PRIZA SHUKO	B	18		0.00
9		FISA SHUKO PENTRU EXTERIOR	B	18		0.00
10		DOZA LEGATURA 100X100X50 IP 55	B	12		0.00
11		MATERIAL AUXILIAR	B	1		0.00
MATERIAL APROVIZIONARE, TRANSPORT, UTILA LUCRU LA INALTIME MANOPERĂ VALOARE T.V.A. TOTAL GENERAL LEI						0.00 19%

Întocmit
Serviciul Tehnic
Ing. Coseri Claudiu

